

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING						FORM 3 AMENDED REPORT				
APPLICATION FOR PERMIT TO DRILL						1. WELL NAME and NUMBER Slade 2-25-2-WH				
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						3. FIELD OR WILDCAT WILDCAT				
4. TYPE OF WELL Oil Well Coalbed Methane Well: NO						5. UNIT or COMMUNITIZATION AGREEMENT NAME				
6. NAME OF OPERATOR NEWFIELD PRODUCTION COMPANY						7. OPERATOR PHONE 435 646-4825				
8. ADDRESS OF OPERATOR Rt 3 Box 3630 , Myton, UT, 84052						9. OPERATOR E-MAIL mcrozier@newfield.com				
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) Patented			11. MINERAL OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>			12. SURFACE OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>				
13. NAME OF SURFACE OWNER (if box 12 = 'fee') Max Leon Ross & Tera Lee S. Ross, Trustees-Ross Family Trust						14. SURFACE OWNER PHONE (if box 12 = 'fee') 435-646-3285				
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee') P.O. Box 757, Roosevelt, UT 84066						16. SURFACE OWNER E-MAIL (if box 12 = 'fee')				
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')			18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>			19. SLANT VERTICAL <input type="checkbox"/> DIRECTIONAL <input type="checkbox"/> HORIZONTAL <input checked="" type="checkbox"/>				
20. LOCATION OF WELL		FOOTAGES		QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN		
LOCATION AT SURFACE		228 FNL 2468 FEL		NWNE	25	2.0 S	2.0 W	U		
Top of Uppermost Producing Zone		660 FNL 1980 FEL		NWNE	25	2.0 S	2.0 W	U		
At Total Depth		660 FSL 1980 FEL		SWSE	25	2.0 S	2.0 W	U		
21. COUNTY DUCESNE			22. DISTANCE TO NEAREST LEASE LINE (Feet) 228			23. NUMBER OF ACRES IN DRILLING UNIT 40				
			25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 3170			26. PROPOSED DEPTH MD: 14196 TVD: 9649				
27. ELEVATION - GROUND LEVEL 5187			28. BOND NUMBER B001834			29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 437478				
Hole, Casing, and Cement Information										
String	Hole Size	Casing Size	Length	Weight	Grade & Thread	Max Mud Wt.	Cement	Sacks	Yield	Weight
COND	17.5	14	0 - 60	37.0	H-40 ST&C	0.0	Class G	35	1.17	15.8
SURF	12.25	9.625	0 - 2500	36.0	J-55 LT&C	8.3	Type III	216	3.33	11.0
							Type III	95	1.9	13.0
I1	8.75	7	0 - 10220	26.0	P-110 Other	10.5	Premium Lite High Strength	350	2.59	11.5
							50/50 Poz	265	1.62	13.0
PROD	6.125	4.5	9312 - 14196	13.5	P-110 Other	10.5	No Used	0	0.0	0.0
ATTACHMENTS										
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES										
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER					<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN					
<input checked="" type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)					<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER					
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)					<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP					
NAME Don Hamilton				TITLE Permitting Agent			PHONE 435 719-2018			
SIGNATURE				DATE 09/18/2012			EMAIL starpoint@etv.net			
API NUMBER ASSIGNED 43013517280000				APPROVAL Permit Manager						

Newfield Production Company**2-25-2-2WH****Surface Hole Location: 228' FNL, 2468' FEL, Section 25, T2S, R2W****Bottom Hole Location: 660' FSL, 1980' FEL, Section 25, T2S, R2W****Duchesne County, UT****Drilling Program****1. Formation Tops**

Uinta	surface
Green River	4,832'
Garden Gulch member	7,741'
Uteland Butte	9,827'
Lateral TD	9,649' TVD / 14,196' MD

2. Depth to Oil, Gas, Water, or Minerals

Base of moderately saline	3,235'	(water)
Green River	7,741' - 9,649'	(oil)

3. Pressure Control**Section BOP Description**

Surface 12-1/4" diverter

Interm/Prod The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc for a 5M system.

A 5M BOP system will consist of 2 ram preventers (double or two singles) and an annular preventer (see attached diagram). A choke manifold rated to at least 5,000 psi will be used.

4. Casing

Description	Interval		Weight (ppf)	Grade	Coupl	Pore Press @ Shoe	MW @ Shoe	Frac Grad @ Shoe	Safety Factors		
	Top	Bottom (TVD/MD)							Burst	Collapse	Tension
Conductor 14	0'	60'	37	H-40	Weld	--	--	--	--	--	--
Surface 9 5/8	0'	2,500'	36	J-55	LTC	8.33	8.33	12	3,520	2,020	453,000
Intermediate 7	0'	9,874' 10,220'	26	P-110	BTC	10	10.5	15	2.51	2.54	5.03
Production 4 1/2	9,312'	9,649' 14,196'	13.5	P-110	BTC	10	10.5	--	9,960	6,210	830,000
									2.40	1.41	3.12
									12,410	10,670	422,000
									3.06	2.48	6.40

Assumptions:

Surface casing MASP = (frac gradient + 1.0 ppg) - (gas gradient)

Intermediate casing MASP = (reservoir pressure) - (gas gradient)

Production casing MASP = (reservoir pressure) - (gas gradient)

All collapse calculations assume fully evacuated casing with a gas gradient

All tension calculations assume air weight of casing

Gas gradient = 0.1 psi/ft

All casing shall be new.

All casing strings shall have a minimum of 1 centralizer on each of the bottom 3 joints.

5. Cement

Job	Hole Size	Fill	Slurry Description	ft ³	OH excess	Weight (ppg)	Yield (ft ³ /sk)
				sacks			
Conductor	17 1/2	60'	Class G w/ 2% KCl + 0.25 lbs/sk Cello Flake	41	15%	15.8	1.17
				35			
Surface Lead	12 1/4	2,000'	Type III + .125 lbs/sk Cello Flakes	720	15%	11.0	3.33
				216			
Surface Tail	12 1/4	500'	Type III + .125 lbs/sk Cello Flakes	180	15%	13.0	1.9
				95			
Intermediate Lead	8 3/4	5,241'	Premium - 65% Class G / 35% Poz + 10% Bentonite	906	15%	11.5	2.59
				350			
Intermediate Tail	8 3/4	2,479'	50/50 Poz/Class G + 1% bentonite	429	15%	13.0	1.62
				265			
Production	6 1/8	--	Liner will not be cemented. It will be isolated with a liner top packer.	--	--	--	--
				--			

The surface casing will be cemented to surface. In the event that cement does not reach surface during the primary cement job, a remedial job will be performed.

Actual cement volumes for the intermediate casing string will be calculated from an open hole caliper log, plus 15% excess.

The cement slurries will be adjusted for hole conditions and blend test results.

The production liner will be left uncemented. Individual frac stages will be isolated with open hole packers. A liner top hanger and packer will be installed 50' above KOP.

6. Type and Characteristics of Proposed Circulating Medium

Interval

Description

Surface - 2,500'

An air and/or fresh water system will be utilized. If an air rig is used, the blooie line discharge may be less than 100' from the wellbore in order to minimize location size. The blooie line is not equipped with an automatic igniter. The air compressor may be located less than 100' from the well bore due to the low possibility of combustion with the air/dust mixture. Water will be on location to be used as kill fluid, if necessary.

2,500' - TD

A water based mud system will be utilized. Hole stability may be improved with additions of KCl or a similar inhibitive substance. In order to control formation pressure the system will be weighted with additions of bentonite, and

if conditions warrant, with barite.

Anticipated maximum mud weight is 10.5 ppg.

7. Logging, Coring, and Testing

Logging: A dual induction, gamma ray, and caliper log will be run in the intermediate section from the top of the curve to the base of the surface casing. A compensated neutron/formation density log will be run in the intermediate section from the top of the curve to the top of the Garden Gulch formation. A cement bond log will be run from the top of the curve to the cement top behind the intermediate casing.

Cores: As deemed necessary.

DST: There are no DST's planned for this well.

8. Anticipated Abnormal Pressure or Temperature

Maximum anticipated bottomhole pressure will be approximately equal to total depth (feet) multiplied by a 0.52 psi/ft gradient.

$$9,649' \times 0.52 \text{ psi/ft} = 5017 \text{ psi}$$

No abnormal temperature is expected. No H₂S is expected.

9. Other Aspects

An 8-3/4" vertical hole will be drilled to a kick off point of 9,362' .

Directional tools will then be used to build to 93.24 degrees inclination.

The 7" intermediate casing string will be set once the well is landed horizontally in the target zone.


The lateral will be drilled to the bottomhole location shown on the plat.

A liner with a system of open hole packers will be used to provide multi-stage frac isolation in the lateral. The top of the liner will be place 50' above KOP and will be isolated with a liner top packer.

Newfield requests the following variances from Onshore Order #2:


- Variance from Onshoer Order #2, III.E.1

Refer to Newfield Production Company Standard Operating Practices "Ute Tribal Green River Development Program" paragraph 9.0

T2S, R2W, U.S.B.&M.**NEWFIELD EXPLORATION COMPANY**


WELL LOCATION, 2-25-2-2WH, LOCATED AS SHOWN IN THE NW 1/4 NE 1/4 OF SECTION 25, T2S, R2W, U.S.B.&M. DUCHESNE COUNTY, UTAH.

TARGET BOTTOM HOLE, 2-25-2-2WH, LOCATED AS SHOWN IN THE SW 1/4 SE 1/4 OF SECTION 25, T2S, R2W, U.S.B.&M. DUCHESNE COUNTY, UTAH.

**NOTES:**

1. Well footages are measured at right angles to the Section Lines.
2. Bearings are based on Global Positioning Satellite observations.
3. The Top of Producing Interval bears $S49^{\circ}37'35''E$ 648.72' from the Top of Hole.

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD BOOKS OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

**TRI STATE LAND SURVEYING & CONSULTING**

180 NORTH VERNAL AVE. - VERNAL, UTAH 84078
(435) 781-2501

DATE SURVEYED: 05-25-12	SURVEYED BY: S.V.	VERSION:
DATE DRAWN: 06-07-12	DRAWN BY: R.B.T.	V1
REVISED:	SCALE: 1" = 1000'	

◆ = SECTION CORNERS LOCATED

BASIS OF ELEV; Elevations are based on an N.G.S. OPUS Correction. LOCATION: LAT. $40^{\circ}04'09.56''$ LONG. $110^{\circ}00'43.28''$ (Tristate Aluminum Cap) Elev. 5281.57'

NAD 83 (SURFACE LOCATION)
LATITUDE = $40^{\circ}17'12.93''$
LONGITUDE = $110^{\circ}03'26.29''$
NAD 27 (SURFACE LOCATION)
LATITUDE = $40^{\circ}17'13.08''$
LONGITUDE = $110^{\circ}03'23.75''$
NAD 83 (BOTTOM HOLE LOCATION)
LATITUDE = $40^{\circ}16'29.54''$
LONGITUDE = $110^{\circ}03'20.10''$
NAD 27 (BOTTOM HOLE LOCATION)
LATITUDE = $40^{\circ}16'29.69''$
LONGITUDE = $110^{\circ}03'17.56''$

Access Road Map

Proposed Location
2-25-2-2WH

See Topo "B"

± 1.8 mi.

± 6.6 mi.

Legend

- Existing Road
— Proposed Road



Tri State
Land Surveying, Inc.

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518



NEWFIELD EXPLORATION COMPANY

2-25-2-2WH
SEC. 25, T2S, R2W, U.S.B.&M.
Duchesne County, UT.


DRAWN BY:	D.C.R.	REVISED:	VERSION:
DATE:	06-07-2012		V1
SCALE:	1:100,000		

TOPOGRAPHIC MAP

SHEET

A

Access Road Map



THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518




NEWFIELD EXPLORATION COMPANY

2-25-2-2WH
SEC. 25, T2S, R2W, U.S.B.&M.
Duchesne County, UT.

DRAWN BY:	D.C.R.	REVISED:	VERSION:
DATE:	06-07-2012		V1
SCALE:	1" = 2,000'		

TOPOGRAPHIC MAP

SHEET
B

Proposed Pipeline Map

THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518

**NEWFIELD EXPLORATION COMPANY**


2-25-2-2WH
SEC. 25, T2S, R2W, U.S.B.&M.
Duchesne County, UT.

DRAWN BY:	D.C.R.	REVISED:	VERSION:
DATE:	06-07-2012		V1
SCALE:	1" = 2,000'		

TOPOGRAPHIC MAP

SHEET

C



THE PARCEL INFORMATION SHOWN HAS NOT BEEN SURVEYED BY TRI-STATE LAND SURVEYING, INC. - TRI-STATE DOES NOT WARRANTY PROPERTY PARCEL DATA OR ANY ASSOCIATED INFORMATION. A PROPERTY SURVEY IS REQUIRED TO DETERMINE THE ACTUAL LOCATION OF PROPERTY LINES AND SHOW ACCURATE DISTANCES ACROSS PARCELS.

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

P: (435) 781-2501
F: (435) 781-2518



NEWFIELD EXPLORATION COMPANY

2-25-2-2WH
SEC. 25, T2S, R2W, U.S.B.&M.
Duchesne County, UT.

DRAWN BY:	D.C.R.	REVISED:	VERSION:
DATE:	06-07-2012		V1
SCALE:	1" = 2,000'		

TOPOGRAPHIC MAP

SHEET

D



Weatherford®

NEWFIELD EXPLORATION CO.

DUCHESNE COUNTY, UT

SLADE 2-25-2-2WH

SLADE 2-25-2-2WH

SLADE 2-25-2-2WH

Plan: PLAN 1

Standard Planning Report

12 September, 2012

CONFIDENTIAL



Weatherford®



Project: DUCHESNE COUNTY, UT
 Site: SLADE 2-25-2-WH
 Well: SLADE 2-25-2-WH
 Wellbore: SLADE 2-25-2-WH
 Design: PLAN 1
 Latitude: 40° 17' 12.930 N
 Longitude: 110° 3' 26.290 W
 GL: 5186.70
 KB: KB @ 5204.70ft (Original Well Elev)



WELLBORE TARGET DETAILS (LAT/LONG)




Name	TVD	+N/-S	+E/-W	Latitude	Longitude	Shape
PBHL - SLADE 2-25-2-WH	9649.00	-4390.57	479.75	40° 16' 29.540 N	110° 3' 20.100 W	Point
LP - SLADE	9874.00	-420.63	494.10	40° 17' 8.773 N	110° 3' 19.914 W	Point

WELL DETAILS: SLADE 2-25-2-WH

+N/-S	+E/-W	Northing	Ground Level:	5186.70	Latitude	Longitude	Slot
0.00	0.00	7276485.84	2042864.58	40° 17' 12.930 N	110° 3' 26.290 W		

SECTION DETAILS

MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	Vsect	Annotation
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
2500.00	0.00	0.00	2500.00	0.00	0.00	0.00	0.00	0.00	Start Build 2.00
2701.88	4.04	74.19	2701.72	1.94	6.64	2.00	74.19	-1.18	Start 6660.02 hold at 2701.88 MD
9361.90	4.04	74.19	9345.20	129.68	458.05	0.00	0.00	-79.16	Start DLS 11.00 TFO 105.76
10219.62	93.24	180.21	9874.00	-420.63	494.10	11.00	105.76	471.81	Start 3976.33 hold at 10219.62 MD
14195.96	93.24	180.21	9649.00	-4390.57	479.75	0.00	0.00	4416.70	TD at 14195.96



CASING DETAILS

TVD	MD	Name	Size
9874.00	10219.62	7"	7"

Plan: PLAN 1 (SLADE 2-25-2-WH/SLADE 2-25-2-WH)

Created By: MATT MAYDEW

Date: 12:43, September 12 2012

**Weatherford®****Weatherford®**

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Well SLADE 2-25-2-ZWH
Company:	NEWFIELD EXPLORATION CO.	TVD Reference:	KB @ 5204.70ft (Original Well Elev)
Project:	DUCHESNE COUNTY, UT	MD Reference:	KB @ 5204.70ft (Original Well Elev)
Site:	SLADE 2-25-2-ZWH	North Reference:	True
Well:	SLADE 2-25-2-ZWH	Survey Calculation Method:	Minimum Curvature
Wellbore:	SLADE 2-25-2-ZWH		
Design:	PLAN 1		

Project	DUCHESNE COUNTY, UT		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	Utah Central Zone		

Site		SLADE 2-25-2-ZWH			
Site Position:		Northing:	7,276,485.84 usft	Latitude:	40° 17' 12.930 N
From:	Lat/Long	Easting:	2,042,864.58 usft	Longitude:	110° 3' 26.290 W
Position Uncertainty:	0.00 ft	Slot Radius:	13-3/16"	Grid Convergence:	0.92 °

Well	SLADE 2-25-2-ZWH					
Well Position	+N/-S	0.00 ft	Northing:	7,276,485.84 usft	Latitude:	40° 17' 12.930 N
	+E/-W	0.00 ft	Easting:	2,042,864.58 usft	Longitude:	110° 3' 26.290 W
Position Uncertainty		0.00 ft	Wellhead Elevation:	ft	Ground Level:	5,186.70 ft

Wellbore	SLADE 2-25-2-ZWH				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	BGGM2012	9/12/2012	11.22	65.94	52,226

Design	PLAN 1			
Audit Notes:				
Version:	Phase:	PLAN	Tie On Depth:	0.00
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)
	0.00	0.00	0.00	173.76

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
2,500.00	0.00	0.00	2,500.00	0.00	0.00	0.00	0.00	0.00	0.00	
2,701.88	4.04	74.19	2,701.72	1.94	6.84	2.00	2.00	0.00	74.19	
9,361.90	4.04	74.19	9,345.20	129.68	458.05	0.00	0.00	0.00	0.00	
10,219.62	93.24	180.21	9,874.00	-420.63	494.10	11.00	10.40	12.36	105.76	LP - SLADE
14,195.96	93.24	180.21	9,649.00	-4,390.57	479.75	0.00	0.00	0.00	0.00	PBHL - SLADE 2-25-2

**Weatherford®****Weatherford®**

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Well SLADE 2-25-2-2WH
Company:	NEWFIELD EXPLORATION CO.	TVD Reference:	KB @ 5204.70ft (Original Well Elev)
Project:	DUCHESNE COUNTY, UT	MD Reference:	KB @ 5204.70ft (Original Well Elev)
Site:	SLADE 2-25-2-2WH	North Reference:	True
Well:	SLADE 2-25-2-2WH	Survey Calculation Method:	Minimum Curvature
Wellbore:	SLADE 2-25-2-2WH		
Design:	PLAN 1		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00
600.00	0.00	0.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00	0.00	0.00
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00	0.00	0.00
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00
1,100.00	0.00	0.00	1,100.00	0.00	0.00	0.00	0.00	0.00	0.00
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0.00	0.00	0.00
1,300.00	0.00	0.00	1,300.00	0.00	0.00	0.00	0.00	0.00	0.00
1,400.00	0.00	0.00	1,400.00	0.00	0.00	0.00	0.00	0.00	0.00
1,500.00	0.00	0.00	1,500.00	0.00	0.00	0.00	0.00	0.00	0.00
1,600.00	0.00	0.00	1,600.00	0.00	0.00	0.00	0.00	0.00	0.00
1,700.00	0.00	0.00	1,700.00	0.00	0.00	0.00	0.00	0.00	0.00
1,800.00	0.00	0.00	1,800.00	0.00	0.00	0.00	0.00	0.00	0.00
1,900.00	0.00	0.00	1,900.00	0.00	0.00	0.00	0.00	0.00	0.00
2,000.00	0.00	0.00	2,000.00	0.00	0.00	0.00	0.00	0.00	0.00
2,100.00	0.00	0.00	2,100.00	0.00	0.00	0.00	0.00	0.00	0.00
2,200.00	0.00	0.00	2,200.00	0.00	0.00	0.00	0.00	0.00	0.00
2,300.00	0.00	0.00	2,300.00	0.00	0.00	0.00	0.00	0.00	0.00
2,400.00	0.00	0.00	2,400.00	0.00	0.00	0.00	0.00	0.00	0.00
Start Build 2.00									
2,500.00	0.00	0.00	2,500.00	0.00	0.00	0.00	0.00	0.00	0.00
2,600.00	2.00	74.19	2,599.98	0.48	1.68	-0.29	2.00	2.00	0.00
Start 6660.02 hold at 2701.88 MD									
2,701.88	4.04	74.19	2,701.72	1.94	6.84	-1.18	2.00	2.00	0.00
2,800.00	4.04	74.19	2,799.59	3.82	13.49	-2.33	0.00	0.00	0.00
2,900.00	4.04	74.19	2,899.34	5.74	20.26	-3.50	0.00	0.00	0.00
3,000.00	4.04	74.19	2,999.09	7.65	27.04	-4.67	0.00	0.00	0.00
3,100.00	4.04	74.19	3,098.84	9.57	33.81	-5.84	0.00	0.00	0.00
3,200.00	4.04	74.19	3,198.60	11.49	40.59	-7.01	0.00	0.00	0.00
3,300.00	4.04	74.19	3,298.35	13.41	47.36	-8.18	0.00	0.00	0.00
3,400.00	4.04	74.19	3,398.10	15.33	54.14	-9.36	0.00	0.00	0.00
3,500.00	4.04	74.19	3,497.85	17.25	60.91	-10.53	0.00	0.00	0.00
3,600.00	4.04	74.19	3,597.60	19.16	67.69	-11.70	0.00	0.00	0.00
3,700.00	4.04	74.19	3,697.36	21.08	74.46	-12.87	0.00	0.00	0.00
3,800.00	4.04	74.19	3,797.11	23.00	81.24	-14.04	0.00	0.00	0.00
3,900.00	4.04	74.19	3,896.86	24.92	88.01	-15.21	0.00	0.00	0.00
4,000.00	4.04	74.19	3,996.61	26.84	94.79	-16.38	0.00	0.00	0.00
4,100.00	4.04	74.19	4,096.36	28.75	101.56	-17.55	0.00	0.00	0.00
4,200.00	4.04	74.19	4,196.11	30.67	108.34	-18.72	0.00	0.00	0.00
4,300.00	4.04	74.19	4,295.87	32.59	115.11	-19.89	0.00	0.00	0.00
4,400.00	4.04	74.19	4,395.62	34.51	121.89	-21.06	0.00	0.00	0.00
4,500.00	4.04	74.19	4,495.37	36.43	128.66	-22.23	0.00	0.00	0.00
4,600.00	4.04	74.19	4,595.12	38.34	135.44	-23.41	0.00	0.00	0.00
4,700.00	4.04	74.19	4,694.87	40.26	142.21	-24.58	0.00	0.00	0.00
4,800.00	4.04	74.19	4,794.63	42.18	148.99	-25.75	0.00	0.00	0.00
4,900.00	4.04	74.19	4,894.38	44.10	155.76	-26.92	0.00	0.00	0.00
5,000.00	4.04	74.19	4,994.13	46.02	162.54	-28.09	0.00	0.00	0.00
5,100.00	4.04	74.19	5,093.88	47.93	169.31	-29.26	0.00	0.00	0.00

**Weatherford®****Weatherford®**

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Well SLADE 2-25-2-2WH
Company:	NEWFIELD EXPLORATION CO.	TVD Reference:	KB @ 5204.70ft (Original Well Elev)
Project:	DUCHESNE COUNTY, UT	MD Reference:	KB @ 5204.70ft (Original Well Elev)
Site:	SLADE 2-25-2-2WH	North Reference:	True
Well:	SLADE 2-25-2-2WH	Survey Calculation Method:	Minimum Curvature
Wellbore:	SLADE 2-25-2-2WH		
Design:	PLAN 1		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
5,200.00	4.04	74.19	5,193.63	49.85	176.09	-30.43	0.00	0.00	0.00
5,300.00	4.04	74.19	5,293.38	51.77	182.86	-31.60	0.00	0.00	0.00
5,400.00	4.04	74.19	5,393.14	53.69	189.64	-32.77	0.00	0.00	0.00
5,500.00	4.04	74.19	5,492.89	55.61	196.41	-33.94	0.00	0.00	0.00
5,600.00	4.04	74.19	5,592.64	57.52	203.19	-35.11	0.00	0.00	0.00
5,700.00	4.04	74.19	5,692.39	59.44	209.96	-36.28	0.00	0.00	0.00
5,800.00	4.04	74.19	5,792.14	61.36	216.74	-37.45	0.00	0.00	0.00
5,900.00	4.04	74.19	5,891.90	63.28	223.51	-38.63	0.00	0.00	0.00
6,000.00	4.04	74.19	5,991.65	65.20	230.29	-39.80	0.00	0.00	0.00
6,100.00	4.04	74.19	6,091.40	67.11	237.06	-40.97	0.00	0.00	0.00
6,200.00	4.04	74.19	6,191.15	69.03	243.84	-42.14	0.00	0.00	0.00
6,300.00	4.04	74.19	6,290.90	70.95	250.61	-43.31	0.00	0.00	0.00
6,400.00	4.04	74.19	6,390.65	72.87	257.39	-44.48	0.00	0.00	0.00
6,500.00	4.04	74.19	6,490.41	74.79	264.16	-45.65	0.00	0.00	0.00
6,600.00	4.04	74.19	6,590.16	76.70	270.94	-46.82	0.00	0.00	0.00
6,700.00	4.04	74.19	6,689.91	78.62	277.71	-47.99	0.00	0.00	0.00
6,800.00	4.04	74.19	6,789.66	80.54	284.49	-49.16	0.00	0.00	0.00
6,900.00	4.04	74.19	6,889.41	82.46	291.26	-50.33	0.00	0.00	0.00
7,000.00	4.04	74.19	6,989.16	84.38	298.04	-51.50	0.00	0.00	0.00
7,100.00	4.04	74.19	7,088.92	86.29	304.81	-52.67	0.00	0.00	0.00
7,200.00	4.04	74.19	7,188.67	88.21	311.59	-53.85	0.00	0.00	0.00
7,300.00	4.04	74.19	7,288.42	90.13	318.36	-55.02	0.00	0.00	0.00
7,400.00	4.04	74.19	7,388.17	92.05	325.14	-56.19	0.00	0.00	0.00
7,500.00	4.04	74.19	7,487.92	93.97	331.91	-57.36	0.00	0.00	0.00
7,600.00	4.04	74.19	7,587.68	95.88	338.69	-58.53	0.00	0.00	0.00
7,700.00	4.04	74.19	7,687.43	97.80	345.46	-59.70	0.00	0.00	0.00
7,800.00	4.04	74.19	7,787.18	99.72	352.24	-60.87	0.00	0.00	0.00
7,900.00	4.04	74.19	7,886.93	101.64	359.01	-62.04	0.00	0.00	0.00
8,000.00	4.04	74.19	7,986.68	103.56	365.79	-63.21	0.00	0.00	0.00
8,100.00	4.04	74.19	8,086.43	105.48	372.56	-64.38	0.00	0.00	0.00
8,200.00	4.04	74.19	8,186.19	107.39	379.34	-65.55	0.00	0.00	0.00
8,300.00	4.04	74.19	8,285.94	109.31	386.11	-66.72	0.00	0.00	0.00
8,400.00	4.04	74.19	8,385.69	111.23	392.88	-67.89	0.00	0.00	0.00
8,500.00	4.04	74.19	8,485.44	113.15	399.66	-69.07	0.00	0.00	0.00
8,600.00	4.04	74.19	8,585.19	115.07	406.43	-70.24	0.00	0.00	0.00
8,700.00	4.04	74.19	8,684.95	116.98	413.21	-71.41	0.00	0.00	0.00
8,800.00	4.04	74.19	8,784.70	118.90	419.98	-72.58	0.00	0.00	0.00
8,900.00	4.04	74.19	8,884.45	120.82	426.76	-73.75	0.00	0.00	0.00
9,000.00	4.04	74.19	8,984.20	122.74	433.53	-74.92	0.00	0.00	0.00
9,100.00	4.04	74.19	9,083.95	124.66	440.31	-76.09	0.00	0.00	0.00
9,200.00	4.04	74.19	9,183.70	126.57	447.08	-77.26	0.00	0.00	0.00
9,300.00	4.04	74.19	9,283.46	128.49	453.86	-78.43	0.00	0.00	0.00
Start DLS 11.00 TFO 105.76									
9,361.90	4.04	74.19	9,345.20	129.68	458.05	-79.16	0.00	0.00	0.00
9,400.00	4.96	128.55	9,383.20	129.02	460.63	-78.22	11.00	2.43	142.68
9,450.00	9.42	155.83	9,432.81	123.93	464.00	-72.79	11.00	8.92	54.56
9,500.00	14.61	164.88	9,481.70	114.10	467.33	-62.66	11.00	10.37	18.10
9,550.00	19.96	169.21	9,529.43	99.62	470.57	-47.91	11.00	10.70	8.65
9,600.00	25.37	171.75	9,575.55	80.62	473.71	-28.69	11.00	10.83	5.09
9,650.00	30.81	173.45	9,619.64	57.28	476.71	-5.16	11.00	10.88	3.39
9,700.00	36.27	174.68	9,661.30	29.81	479.55	22.46	11.00	10.92	2.46
9,750.00	41.74	175.62	9,700.14	-1.54	482.19	53.91	11.00	10.94	1.89
9,800.00	47.22	176.38	9,735.80	-36.47	484.62	88.90	11.00	10.95	1.52
9,850.00	52.69	177.02	9,767.96	-74.67	486.82	127.11	11.00	10.96	1.28

**Weatherford****Weatherford**

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Well SLADE 2-25-2-2WH
Company:	NEWFIELD EXPLORATION CO.	TVD Reference:	KB @ 5204.70ft (Original Well Elev)
Project:	DUCHESNE COUNTY, UT	MD Reference:	KB @ 5204.70ft (Original Well Elev)
Site:	SLADE 2-25-2-2WH	North Reference:	True
Well:	SLADE 2-25-2-2WH	Survey Calculation Method:	Minimum Curvature
Wellbore:	SLADE 2-25-2-2WH		
Design:	PLAN 1		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
9,900.00	58.17	177.57	9,796.32	-115.79	488.75	168.19	11.00	10.96	1.10
9,950.00	63.66	178.06	9,820.61	-159.43	490.41	211.76	11.00	10.97	0.98
10,000.00	69.14	178.50	9,840.62	-205.21	491.78	257.42	11.00	10.97	0.89
10,050.00	74.63	178.92	9,856.16	-252.70	492.85	304.74	11.00	10.97	0.83
10,100.00	80.12	179.31	9,867.09	-301.47	493.60	353.30	11.00	10.97	0.78
10,150.00	85.60	179.69	9,873.30	-351.06	494.04	402.65	11.00	10.97	0.76
10,200.00	91.09	180.06	9,874.74	-401.02	494.15	452.32	11.00	10.97	0.75
Start 3976.33 hold at 10219.62 MD - 7" - LP - SLADE									
10,219.62	93.24	180.21	9,874.00	-420.63	494.10	471.81	11.00	10.97	0.75
10,300.00	93.24	180.21	9,869.45	-500.88	493.81	551.55	0.00	0.00	0.00
10,400.00	93.24	180.21	9,863.79	-600.72	493.45	650.76	0.00	0.00	0.00
10,500.00	93.24	180.21	9,858.13	-700.56	493.09	749.97	0.00	0.00	0.00
10,600.00	93.24	180.21	9,852.48	-800.39	492.73	849.18	0.00	0.00	0.00
10,700.00	93.24	180.21	9,846.82	-900.23	492.37	948.39	0.00	0.00	0.00
10,800.00	93.24	180.21	9,841.16	-1,000.07	492.01	1,047.60	0.00	0.00	0.00
10,900.00	93.24	180.21	9,835.50	-1,099.91	491.65	1,146.81	0.00	0.00	0.00
11,000.00	93.24	180.21	9,829.84	-1,199.75	491.28	1,246.02	0.00	0.00	0.00
11,100.00	93.24	180.21	9,824.18	-1,299.59	490.92	1,345.23	0.00	0.00	0.00
11,200.00	93.24	180.21	9,818.53	-1,399.43	490.56	1,444.44	0.00	0.00	0.00
11,300.00	93.24	180.21	9,812.87	-1,499.27	490.20	1,543.64	0.00	0.00	0.00
11,400.00	93.24	180.21	9,807.21	-1,599.11	489.84	1,642.85	0.00	0.00	0.00
11,500.00	93.24	180.21	9,801.55	-1,698.95	489.48	1,742.06	0.00	0.00	0.00
11,600.00	93.24	180.21	9,795.89	-1,798.79	489.12	1,841.27	0.00	0.00	0.00
11,700.00	93.24	180.21	9,790.23	-1,898.62	488.76	1,940.48	0.00	0.00	0.00
11,800.00	93.24	180.21	9,784.57	-1,998.46	488.40	2,039.69	0.00	0.00	0.00
11,900.00	93.24	180.21	9,778.92	-2,098.30	488.04	2,138.90	0.00	0.00	0.00
12,000.00	93.24	180.21	9,773.26	-2,198.14	487.68	2,238.11	0.00	0.00	0.00
12,100.00	93.24	180.21	9,767.60	-2,297.98	487.32	2,337.32	0.00	0.00	0.00
12,200.00	93.24	180.21	9,761.94	-2,397.82	486.96	2,436.53	0.00	0.00	0.00
12,300.00	93.24	180.21	9,756.28	-2,497.66	486.59	2,535.74	0.00	0.00	0.00
12,400.00	93.24	180.21	9,750.62	-2,597.50	486.23	2,634.95	0.00	0.00	0.00
12,500.00	93.24	180.21	9,744.97	-2,697.34	485.87	2,734.15	0.00	0.00	0.00
12,600.00	93.24	180.21	9,739.31	-2,797.18	485.51	2,833.36	0.00	0.00	0.00
12,700.00	93.24	180.21	9,733.65	-2,897.02	485.15	2,932.57	0.00	0.00	0.00
12,800.00	93.24	180.21	9,727.99	-2,996.86	484.79	3,031.78	0.00	0.00	0.00
12,900.00	93.24	180.21	9,722.33	-3,096.69	484.43	3,130.99	0.00	0.00	0.00
13,000.00	93.24	180.21	9,716.67	-3,196.53	484.07	3,230.20	0.00	0.00	0.00
13,100.00	93.24	180.21	9,711.01	-3,296.37	483.71	3,329.41	0.00	0.00	0.00
13,200.00	93.24	180.21	9,705.36	-3,396.21	483.35	3,428.62	0.00	0.00	0.00
13,300.00	93.24	180.21	9,699.70	-3,496.05	482.99	3,527.83	0.00	0.00	0.00
13,400.00	93.24	180.21	9,694.04	-3,595.89	482.63	3,627.04	0.00	0.00	0.00
13,500.00	93.24	180.21	9,688.38	-3,695.73	482.27	3,726.25	0.00	0.00	0.00
13,600.00	93.24	180.21	9,682.72	-3,795.57	481.90	3,825.46	0.00	0.00	0.00
13,700.00	93.24	180.21	9,677.06	-3,895.41	481.54	3,924.67	0.00	0.00	0.00
13,800.00	93.24	180.21	9,671.41	-3,995.25	481.18	4,023.87	0.00	0.00	0.00
13,900.00	93.24	180.21	9,665.75	-4,095.09	480.82	4,123.08	0.00	0.00	0.00
14,000.00	93.24	180.21	9,660.09	-4,194.92	480.46	4,222.29	0.00	0.00	0.00
14,100.00	93.24	180.21	9,654.43	-4,294.76	480.10	4,321.50	0.00	0.00	0.00
TD at 14195.96 - PBHL - SLADE 2-25-2-2WH									
14,195.96	93.24	180.21	9,649.00	-4,390.57	479.75	4,416.70	0.00	0.00	0.00

**Weatherford®****Weatherford®**

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Well SLADE 2-25-2-2WH
Company:	NEWFIELD EXPLORATION CO.	TVD Reference:	KB @ 5204.70ft (Original Well Elev)
Project:	DUCHESNE COUNTY, UT	MD Reference:	KB @ 5204.70ft (Original Well Elev)
Site:	SLADE 2-25-2-2WH	North Reference:	True
Well:	SLADE 2-25-2-2WH	Survey Calculation Method:	Minimum Curvature
Wellbore:	SLADE 2-25-2-2WH		
Design:	PLAN 1		

Design Targets										
Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude	
PBHL - SLADE 2-25-2-2 - hit/miss target - Shape	0.00	0.00	9,649.00	-4,390.57	479.75	7,272,103.60	2,043,415.08	40° 16' 29.540 N	110° 3' 20.100 W	
LP - SLADE - plan hits target center - Point	0.00	0.00	9,874.00	-420.63	494.10	7,276,073.24	2,043,365.40	40° 17' 8.773 N	110° 3' 19.914 W	

Casing Points					
Measured Depth (ft)	Vertical Depth (ft)	Name	Casing Diameter (")	Hole Diameter (")	
10,219.62	9,874.00	7"	7	8-3/4	

Plan Annotations					
Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates			
		+N/-S (ft)	+E/-W (ft)	Comment	
2,500.00	2,500.00	0.00	0.00	Start Build 2.00	
2,701.88	2,701.72	1.94	6.84	Start 6660.02 hold at 2701.88 MD	
9,361.90	9,345.20	129.68	458.05	Start DLS 11.00 TFO 105.76	
10,219.62	9,874.00	-420.63	494.10	Start 3976.33 hold at 10219.62 MD	
14,195.96	9,649.00	-4,390.57	479.75	TD at 14195.96	

**AFFIDAVIT OF EASEMENT, RIGHT-OF-WAY AND
SURFACE USE AGREEMENT**

Shane Gillespie personally appeared before me, being duly sworn, deposes and with respect to State of Utah R649-3-34.7 says:

1. My name is Shane Gillespie. I am a Landman for Newfield Production Company, whose address is 1001 17th Street, Suite 2000, Denver, CO 80202 ("Newfield").
2. Newfield is the Operator of the proposed Slade 2-25-2-2WH well with a surface location to be positioned in the NWNE of Section 25, Township 2 South, Range 2 West, Duchesne County, Utah (the "Drillsite Location"), and a bottom hole location to be positioned in the SWSE of Section 25, Township 2 South, Range 2 West, Duchesne County, Utah. The surface owner of the Drillsite Location is Max Leon Ross and Tera Lee S. Ross, Trustees of the Ross Family Trust, dated the 13th day of October 2004, whose address is P.O. Box 757, Roosevelt, UT 84066 ("Surface Owner").
3. Newfield and the Surface Owner have agreed upon an Easement, Right-of-Way and Surface Use Agreement dated June 1, 2012 covering the Drillsite Location and access to the Drillsite Location.

FURTHER AFFIANT SAYETH NOT.



Shane Gillespie

ACKNOWLEDGEMENT


STATE OF COLORADO §
 §
COUNTY OF DENVER §

Before me, a Notary Public, in and for the State, on this 3rd day of July, 2012, personally appeared Shane Gillespie, to me known to be the identical person who executed the foregoing instrument, and acknowledged to me that he executed the same as his own free and voluntary act and deed for the uses and purposes therein set forth.




NOTARY PUBLIC


My Commission Expires:



Typical 5M BOP stack configuration



Typical 5M choke manifold configuration



NEWFIELD EXPLORATION COMPANY**WELL PAD INTERFERENCE PLAT****2-25-2-2WH****Pad Location: NWNE Section 25, T2S, R2W, U.S.B.&M.**1981
Aluminum
Cap

Sec. 24

Sec. 25

Section Line

Proposed
Access**TOP HOLE FOOTAGES**

2-25-2-2WH

228' FNL & 2468' FEL

**TOP OF PRODUCING
INTERVAL FOOTAGES**

2-25-2-2WH

660' FNL & 1980' FEL

BOTTOM HOLE FOOTAGES

2-25-2-2WH

660' FSL & 1980' FEL

Exist. 2-Track Road

Edge of
Proposed
Pad

Proposed Pit

2-25-2-2WH

S07°09'47"E - 4418.48'
(To Bottom Hole)S49°37'35"E - 648.72'
(To Top of Producing Interval)**LATITUDE & LONGITUDE
Surface Position of Wells (NAD 83)**

WELL	LATITUDE	LONGITUDE
2-25-2-2WH	40° 17' 12.93"	110° 03' 26.29"

**LATITUDE & LONGITUDE
Bottom Hole Position (NAD 83)**

WELL	LATITUDE	LONGITUDE
2-25-2-2WH	40° 16' 29.54"	110° 03' 20.10"

Note:Bearings are based
on GPS Observations.**RELATIVE COORDINATES
From Top Hole to Bottom Hole**

WELL	NORTH	EAST
2-25-2-2WH	-4,384'	551'

SURVEYED BY: S.V.	DATE SURVEYED: 05-25-12	VERSION:
DRAWN BY: R.B.T.	DATE DRAWN: 06-07-12	V1
SCALE: 1" = 60'	REVISED:	

Tri State (435) 781-2501
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078


RECEIVED: September 18, 2012

NEWFIELD EXPLORATION COMPANY**PROPOSED LOCATION LAYOUT****2-25-2-2WH****Pad Location: NWNE Section 25, T2S, R2W, U.S.B.&M.****TOPSOIL STOCKPILE**

Approx. Height = 4' Max.
 Approx. Area = 21,277 Sq. Ft.
 ±2,780 Cu. Yds.

EXCESS MATERIAL

Approx. Dims. = 110'x60'x10'
 Approx. Area = 6,309 Sq. Ft.
 ±1,560 Cu. Yds.





**NOTE:**

The topsoil & excess material areas are calculated as being mounds containing 4,340 cubic yards of dirt (a 10% fluff factor is included). The mound areas are calculated with push slopes of 1.5:1 & fall slopes of 1.5:1.

SURVEYED BY: S.V.	DATE SURVEYED: 05-25-12	VERSION:
DRAWN BY: R.B.T.	DATE DRAWN: 06-07-12	V1
SCALE: 1" = 60'	REVISED:	

Tri State
 Land Surveying, Inc.
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078
 (435) 781-2501

RECEIVED: September 18, 2012

NEWFIELD EXPLORATION COMPANY**CROSS SECTIONS****2-25-2-2WH***Pad Location: NWNE Section 25, T2S, R2W, U.S.B.&M.*

NOTE:
UNLESS OTHERWISE
NOTED ALL CUT/FILL
SLOPES ARE AT 1.5:1

ESTIMATED EARTHWORK QUANTITIES
(No Shrink or swell adjustments have been used)
(Expressed in Cubic Yards)

ITEM	CUT	FILL	6" TOPSOIL	EXCESS
PAD	7,760	7,760	Topsoil is not included in Pad Cut Volume	0
PIT	1,420	0		1,420
TOTALS	9,180	7,760	2,530	1,420



SURVEYED BY: S.V.	DATE SURVEYED: 05-25-12	VERSION:
DRAWN BY: R.B.T.	DATE DRAWN: 06-07-12	V1
SCALE: 1" = 60'	REVISED:	

Tri State (435) 781-2501
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

RECEIVED: September 18, 2012

NEWFIELD EXPLORATION COMPANY**TYPICAL RIG LAYOUT****2-25-2-2WH**


Pad Location: NWNE Section 25, T2S, R2W, U.S.B.&M.



SURVEYED BY: S.V.	DATE SURVEYED: 05-25-12	VERSION:
DRAWN BY: R.B.T.	DATE DRAWN: 06-07-12	V1
SCALE: 1" = 60'	REVISED:	


Tri State (435) 781-2501
Land Surveying, Inc.
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078

RECEIVED: September 18, 2012



API Number: 4301351728
Well Name: Slade 2-25-2-2WH
Township T02.0S Range R02.0W Section 25
Meridian: UBM
Operator: NEWFIELD PRODUCTION COMPANY
 Map Prepared:
 Map Produced by Diana Mason

Units	Wells Query
STATUS	Status
ACTIVE	APD - Approved Permit
EXPLORATORY	DRL - Spudded (Drilling Commenced)
GAS STORAGE	GIW - Gas Injection
NF PP OIL	GS - Gas Storage
NF SECONDARY	LOC - New Location
PI OIL	OPS - Operation Suspended
PP GAS	PA - Plugged Abandoned
PP GEOTHERM	PGW - Producing Gas Well
PP OIL	POW - Producing Oil Well
SECONDARY	SGW - Shut-in Gas Well
TERMINATED	SOW - Shut-in Oil Well
Fields	TA - Temp. Abandoned
Unknown	TW - Test Well
ABANDONED	WDW - Water Disposal
ACTIVE	WW - Water Injection Well
COMBINED	WSW - Water Supply Well
INACTIVE	Bottom Hole Location - Oil/Gas/Dib
STORAGE	
TERMINATED	



Well Name	NEWFIELD PRODUCTION COMPANY Slade 2-25-2-2WH 4301351728			
String	COND	SURF	I1	PROD
Casing Size(in)	14.000	9.625	7.000	4.500
Setting Depth (TVD)	60	2500	9874	9649
Previous Shoe Setting Depth (TVD)	0	60	2500	9874
Max Mud Weight (ppg)	8.3	8.3	10.5	10.5
BOPE Proposed (psi)	0	500	5000	5000
Casing Internal Yield (psi)	1000	3520	9950	12410
Operators Max Anticipated Pressure (psi)	5017			10.0

Calculations	COND String	14.000	"
Max BHP (psi)	.052*Setting Depth*MW=	26	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	19	NO
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	13	NO
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	13	NO
Required Casing/BOPE Test Pressure=		60	psi
*Max Pressure Allowed @ Previous Casing Shoe=		0	psi *Assumes 1psi/ft frac gradient


Calculations	SURF String	9.625	"
Max BHP (psi)	.052*Setting Depth*MW=	1079	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	779	NO diverter
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	529	NO OK
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	542	NO Reasonable for area
Required Casing/BOPE Test Pressure=		2464	psi
*Max Pressure Allowed @ Previous Casing Shoe=		60	psi *Assumes 1psi/ft frac gradient

Calculations	I1 String	7.000	"
Max BHP (psi)	.052*Setting Depth*MW=	5391	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	4206	YES
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	3219	YES OK
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	3769	NO OK
Required Casing/BOPE Test Pressure=		5000	psi
*Max Pressure Allowed @ Previous Casing Shoe=		2500	psi *Assumes 1psi/ft frac gradient

Calculations	PROD String	4.500	"
Max BHP (psi)	.052*Setting Depth*MW=	5268	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	4110	YES
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	3145	YES OK
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	5318	YES
Required Casing/BOPE Test Pressure=		5000	psi
*Max Pressure Allowed @ Previous Casing Shoe=		9874	psi *Assumes 1psi/ft frac gradient

43013517280000 Slade 2-25-2-WH

Casing Schematic



Well name:	43013517280000 Slade 2-25-2-2WH	
Operator:	NEWFIELD PRODUCTION COMPANY	
String type:	Surface	Project ID: 43-013-51728
Location:	DUCHESNE COUNTY	

Design parameters:**Collapse**

Mud weight: 8.330 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 109 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 100 ft

Cement top: 774 ft

Burst

Max anticipated surface pressure: 1,950 psi
Internal gradient: 0.220 psi/ft
Calculated BHP 2,500 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.70 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on air weight.
Neutral point: 2,192 ft

Non-directional string.**Re subsequent strings:**

Next setting depth: 9,874 ft
Next mud weight: 10.500 ppg
Next setting BHP: 5,386 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 2,500 ft
Injection pressure: 2,500 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	2500	9.625	36.00	J-55	LT&C	2500	2500	8.796	20442
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	1082	2020	1.867	2500	3520	1.41	90	453	5.03 J

Prepared Helen Sadik-Macdonald
by: Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: November 29, 2012
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 2500 ft, a mud weight of 8.33 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Well name:	43013517280000 Slade 2-25-2-WH	
Operator:	NEWFIELD PRODUCTION COMPANY	
String type:	Intermediate	Project ID: 43-013-51728
Location:	DUCESNE COUNTY	

Design parameters:**Collapse**

Mud weight: 10.500 ppg
Internal fluid density: 1.000 ppg

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H₂S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 212 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,000 ft

Cement top: 5,013 ft

Burst

Max anticipated surface pressure: 3,214 psi
Internal gradient: 0.220 psi/ft
Calculated BHP 5,386 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.60 (B)

Tension is based on air weight.
Neutral point: 8,324 ft

Directional Info - Build & Build

Kick-off point: 2500 ft
Departure at shoe: 649 ft
Maximum dogleg: 11 °/100ft
Inclination at shoe: 93.24 °

Re subsequent strings:

Next setting depth: 9,874 ft
Next mud weight: 10.500 ppg
Next setting BHP: 5,386 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 9,874 ft
Injection pressure: 9,874 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	10220	7	26.00	P-110	Buttress	9874	10220	6.151	113657
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	4873	6230	1.279	5386	9950	1.85	256.7	830.4	3.23 B

Prepared by: Helen Sadik-Macdonald
Div of Oil, Gas & Mining

Phone: 801-538-5357
FAX: 801-359-3940

Date: November 29, 2012
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 9874 ft, a mud weight of 10.5 ppg. An internal gradient of .052 psi/ft was used for collapse from TD. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Well name:	43013517280000 Slade 2-25-2-WH	
Operator:	NEWFIELD PRODUCTION COMPANY	
String type:	Production Liner	Project ID: 43-013-51728
Location:	DUCHESE COUNTY	

Design parameters:**Collapse**

Mud weight: 10.500 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 209 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,000 ft

Burst:

Design factor 1.00

Burst

Max anticipated surface pressure: 3,140 psi
Internal gradient: 0.220 psi/ft
Calculated BHP 5,263 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.60 (B)

Tension is based on air weight.
Neutral point: 9,678 ft

Liner top: 9,649 ft

Directional Info - Build & Build

Kick-off point: 2500 ft
Departure at shoe: 4417 ft
Maximum dogleg: 11 °/100ft
Inclination at shoe: 93.24 °

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	4596	4.5	13.50	P-110	Buttress	9649	14196	3.795	27573
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	5263	10680	2.029	5313	12410	2.34	1	421.9	99.99 B

Prepared by: Helen Sadik-Macdonald
Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: November 29, 2012
Salt Lake City, Utah

Remarks:

For this liner string, the top is rounded to the nearest 100 ft. Collapse is based on a vertical depth of 9649 ft, a mud weight of 10.5 ppg. The Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Engineering responsibility for use of this design will be that of the purchaser.



September 18, 2012

State of Utah
Division of Oil, Gas & Mining
ATTN: Brad Hill
P O Box 145801
Salt Lake City, UT 84114

RE: **Slade 2-25-2-2WH**
Section 9, T2S, R2W
Duchesne County, Utah

Mr. Hill,

Newfield Production Company ("Newfield") proposes to drill the Slade 2-25-2-2WH from a surface location of 228' FNL & 2468' FEL of Section 25, T2S, R2W. Newfield shall case and cement the Slade 2-25-2-2WH wellbore from the surface location to the point where the wellbore reaches the legal setback of 660' FNL of Section 25, T2S, R2W. The cased and cemented portion of the wellbore shall be neither perforated nor produced. In the event a future recompletion into the cased and cemented portion of the wellbore is proposed, Newfield shall file the appropriate application with the State of Utah.

Due to the above circumstances, Newfield respectfully requests that DOGM administratively grant an exception location for the Slade 2-25-2-2WH.

If you have any questions or require further information, please do not hesitate to contact the undersigned at 303-382-4466 or by email at rnmillier@newfield.com. Your consideration of this matter is greatly appreciated.

Sincerely,

A handwritten signature in blue ink, reading "Robert N. Miller II".

Robert N. Miller II
Landman

ON-SITE PREDRILL EVALUATION

Utah Division of Oil, Gas and Mining

Operator NEWFIELD PRODUCTION COMPANY
Well Name Slade 2-25-2-2WH
API Number 43013517280000 **APD No** 6868 **Field/Unit** WILDCAT
Location:
1/4, 1/4 NWNE **Sec** 25 **Tw** 2.0S **Rng** 2.0W 228 FNL 2468 FEL
GPS Coord
(UTM) 580129 4460033 **Surface Owner** Max Leon Ross & Tera Lee S. Ross,
 Trustees-Ross Family Trust

Participants

Tim Eaton, Forrest Bird - Newfield

Regional/Local Setting & Topography

The proposed location is situated on fallow ground approximately 1 mile North of Hwy 40 as it approaches the City of Roosevelt behind the major industrial area of the town. This part of the area is known as Hancock Cove. The topography is quite flat and has red sandy soils that slopes Northerly to some mapped springs. Regionally, very much of the surrounding lands are used for farming and have seen development for petroleum extraction.

Surface Use Plan

Current Surface Use
Industrial

New Road Miles	Well Pad	Src Const Material	Surface Formation
0.4469	Width 300 Length 400	Offsite	UNTA

Ancillary Facilities N

Waste Management Plan Adequate? Y

Environmental Parameters

Affected Floodplains and/or Wetlands N

Flora / Fauna

High desert shrubland ecosystem. Expected vegetation consists of black sagebrush, shadscale, Atriplex spp., mustard spp, rabbit brush, horsebrush, broom snakeweed, Opuntia spp and spring annuals.

Dominant vegetation;

Galletta, sage, greasewood and Opuntia spp surround the proposed site.

Wildlife;

Adjacent habitat contains forbs that may be suitable browse for deer, antelope, prairie dogs or rabbits, though none were observed.

Soil Type and Characteristics

Red sands sloping generally North to a wash incised by mapped springs

Erosion Issues Y

sandy soils are highly erodible

Sedimentation Issues Y**Site Stability Issues Y**

materials to be imported

Drainage Diversion Required? N**Berm Required? Y****Erosion Sedimentation Control Required? N**

No drainages across location

Paleo Survey Run? Y Paleo Potential Observed? N Cultural Survey Run? Y Cultural Resources? N**Reserve Pit****Site-Specific Factors****Site Ranking****Distance to Groundwater (feet)** 75 to 100 10**Distance to Surface Water (feet)** 200 to 300 10**Dist. Nearest Municipal Well (ft)** 1320 to 5280 5**Distance to Other Wells (feet)** >1320 0**Native Soil Type** High permeability 20**Fluid Type** Fresh Water 5**Drill Cuttings** Normal Rock 0**Annual Precipitation (inches)** 10 to 20 5**Affected Populations****Presence Nearby Utility Conduits Present** 15**Final Score** 70 1 Sensitivity Level**Characteristics / Requirements**

A 40' x 80' x 8' deep reserve pit is planned in an area of cut on the northwest side of the location. A pit liner is required. Newfield commonly uses a 30 mil liner with a felt underliner. Pit should be fenced to prevent entry by deer, other wildlife and domestic animals. Pit to be closed within one year after drilling activities are complete.

Closed Loop Mud Required? N Liner Required? Y Liner Thickness 16 Pit Underlayment Required? Y**Other Observations / Comments**Chris Jensen
Evaluator10/10/2012
Date / Time

Application for Permit to Drill

Statement of Basis

Utah Division of Oil, Gas and Mining

APD No	API WellNo	Status	Well Type	Surf Owner	CBM
6868	43013517280000	LOCKED	OW	P	No
Operator	NEWFIELD PRODUCTION COMPANY		Surface Owner-APD	Max Leon Ross & Tera Lee S. Ross, Trustees-Ross Family Trust	
Well Name	Slade 2-25-2-2WH		Unit		
Field	WILDCAT		Type of Work	DRILL	
Location	NWNE 25 2S 2W U 228 FNL 2468 FEL GPS Coord (UTM) 580131E 4459993N				

Geologic Statement of Basis

Newfield proposes to set 60' of conductor and 2,500' of surface casing at this location. The base of the moderately saline water at this location is estimated to be at a depth of 2,900'. A search of Division of Water Rights records shows over 50 water wells within a 10,000 foot radius of the center of Section 25. Depth is listed as ranging from 60 to 800 feet. Depths are not listed for 3 wells. Average depth is around 150 feet. Water use is listed as irrigation, stock watering, industrial and domestic use. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. The proposed casing and cement should adequately protect ground water in this area.

Brad Hill
APD Evaluator

11/14/2012
Date / Time

Surface Statement of Basis

Location is proposed in a good location although outside the spacing window as it is a horizontal well. Access road enters the pad from the South. The Operator is, in this case, the landowner and its representative was in attendance for the pre-site inspection. The soil type and topography at present do combine to pose a significant threat to erosion or sediment/ pollution transport in these regional climate conditions and mapped springs are found below.

Construction standards of the Operator do appear to be adequate for the proposed purpose as Operator has verbally affirmed plans for importing materials, using a geogrid or compacting native soils to improve stability. Fill slopes are planned under areas planned to support a bank of storage tanks.

I recognize no special flora or animal species or cultural resources on site that the proposed action may harm. The location was previously surveyed for cultural and paleontological resources as the operator saw fit. Outlaw Engineering is going to clear the site for TES species.

The location should be bermed to prevent spills from leaving the confines of the pad. Fencing around the reserve pit will be necessary once the well is drilled to prevent wildlife and livestock from entering. A synthetic liner of 30 mils (minimum) should be utilized in the reserve pit.

Chris Jensen
Onsite Evaluator

10/10/2012
Date / Time

Conditions of Approval / Application for Permit to Drill

Category	Condition
Pits	A synthetic liner with a minimum thickness of 30 mils with a felt subliner shall be properly installed and maintained in the reserve pit.
Surface	The reserve pit shall be fenced upon completion of drilling operations.
Surface	The well site shall be bermed to prevent fluids from leaving the pad.

CONFIDENTIAL

WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 9/18/2012

API NO. ASSIGNED: 43013517280000

WELL NAME: Slade 2-25-2-2WH

OPERATOR: NEWFIELD PRODUCTION COMPANY (N2695)

PHONE NUMBER: 435 719-2018

CONTACT: Don Hamilton

PROPOSED LOCATION: NWNE 25 020S 020W

Permit Tech Review: ☒

SURFACE: 0228 FNL 2468 FEL

Engineering Review: ☒

BOTTOM: 0660 FSL 1980 FEL

Geology Review: ☒

COUNTY: DUCHESNE

LATITUDE: 40.28659

LONGITUDE: -110.05731

UTM SURF EASTINGS: 580131.00

NORTHINGS: 4459993.00

FIELD NAME: WILDCAT

LEASE TYPE: 4 - Fee

LEASE NUMBER: Patented

PROPOSED PRODUCING FORMATION(S): GREEN RIVER

SURFACE OWNER: 4 - Fee

COALBED METHANE: NO

RECEIVED AND/OR REVIEWED:

LOCATION AND SITING:

☒ PLAT☐ R649-2-3.☒ Bond: STATE - B001834

Unit:

☐ Potash☐ R649-3-2. General☐ Oil Shale 190-5☐ Oil Shale 190-3☒ R649-3-3. Exception☐ Oil Shale 190-13☒ Drilling Unit☒ Water Permit: 437478

Board Cause No: Cause 139-90

☐ RDCC Review:

Effective Date: 5/9/2012

☒ Fee Surface Agreement

Siting: 4 Producing Grrv-Wstc Wells In Sec Drl Unit

☐ Intent to Commingle☐ R649-3-11. Directional Drill

Commingle Approved

Comments: Presite Completed

Stipulations: 1 - Exception Location - bhill
5 - Statement of Basis - bhill
10 - Cement Ground Water - hmacdonald
25 - Surface Casing - hmacdonald
27 - Other - bhill

RECEIVED: December 18, 2012



GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: Slade 2-25-2-2WH

API Well Number: 43013517280000

Lease Number: Patented

Surface Owner: FEE (PRIVATE)

Approval Date: 12/18/2012

Issued to:

NEWFIELD PRODUCTION COMPANY , Rt 3 Box 3630 , Myton, UT 84052

Authority:

Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 139-90. The expected producing formation or pool is the GREEN RIVER Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

Exception Location:

Appropriate information has been submitted to DOGM and administrative approval of the requested exception location is hereby granted.

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

In accordance with Utah Admin. R.649-3-21, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

The 5 ½" casing string cement shall be brought back to ±2300' to isolate base of moderately saline ground water.

Surface casing shall be cemented to the surface.

Additional Approvals:

The operator is required to obtain approval from the Division of Oil, Gas and mining before performing any of the following actions during the drilling of this well:

- Any changes to the approved drilling plan - contact Dustin Doucet
- Significant plug back of the well - contact Dustin Doucet
- Plug and abandonment of the well - contact Dustin Doucet

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well - contact Carol Daniels
OR
submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website
at <http://oilgas.ogm.utah.gov>
- 24 hours prior to testing blowout prevention equipment - contact Dan Jarvis
- 24 hours prior to cementing or testing casing - contact Dan Jarvis
- Within 24 hours of making any emergency changes to the approved drilling program
 - contact Dustin Doucet
- 24 hours prior to commencing operations to plug and abandon the well - contact Dan Jarvis

Contact Information:

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voicemail message if the person is not available to take the call):

- Carol Daniels 801-538-5284 - office
- Dustin Doucet 801-538-5281 - office
801-733-0983 - after office hours
- Dan Jarvis 801-538-5338 - office
801-231-8956 - after office hours

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) - due within 5 days of spudding the well
- Monthly Status Report (Form 9) - due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) - due prior to implementation
- Written Notice of Emergency Changes (Form 9) - due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) - due prior to implementation
- Report of Water Encountered (Form 7) - due within 30 days after completion
- Well Completion Report (Form 8) - due within 30 days after completion or plugging

Approved By:

Approved By:

A handwritten signature in black ink, appearing to read 'J. Rogers', written over a light blue horizontal line.

For John Rogers
Associate Director, Oil & Gas

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: Patented
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Oil Well		8. WELL NAME and NUMBER: Slade 2-25-2-WH
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		9. API NUMBER: 43013517280000
3. ADDRESS OF OPERATOR: 1001 17th Street, Suite 2000, Denver, CO, 80202		9. FIELD and POOL or WILDCAT: WILDCAT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0228 FNL 2468 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNE Section: 25 Township: 02.0S Range: 02.0W Meridian: U		COUNTY: DUCHESNE
		STATE: UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 12/1/2013	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER: <input type="text"/>
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:			
<input type="checkbox"/> SPUD REPORT Date of Spud:			
<input type="checkbox"/> DRILLING REPORT Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

This sundry is being submitted to request an extension to this APD that expires on 12/18/2013.

**Approved by the
Utah Division of
Oil, Gas and Mining**

Date: November 18, 2013

By: 

NAME (PLEASE PRINT) Melissa Luke	PHONE NUMBER 303 323-9769	TITLE Regulatory Technician
SIGNATURE N/A		DATE 11/13/2013



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43013517280000

API: 43013517280000

Well Name: Slade 2-25-2-2WH

Location: 0228 FNL 2468 FEL QTR NWNE SEC 25 TWNP 020S RNG 020W MER U

Company Permit Issued to: NEWFIELD PRODUCTION COMPANY

Date Original Permit Issued: 12/18/2012

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☒ Yes ☐ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

Signature: Melissa Luke

Date: 11/13/2013

Title: Regulatory Technician **Representing:** NEWFIELD PRODUCTION COMPANY

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: Patented
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Oil Well	8. WELL NAME and NUMBER: Slade 2-25-2-WH	
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY	9. API NUMBER: 43013517280000	
3. ADDRESS OF OPERATOR: 1001 17th Street, Suite 2000, Denver, CO, 80202	PHONE NUMBER: 303 382-4443 Ext	9. FIELD and POOL or WILDCAT: WILDCAT
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0228 FNL 2468 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNE Section: 25 Township: 02.0S Range: 02.0W Meridian: U	COUNTY: DUCHESNE	
		STATE: UTAH

11.


CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 12/19/2014 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> APD EXTENSION OTHER: <input type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

This sundry notice is being submitted to request an extension to this APD that expires on 12/18/2014.

Approved by the
November 05, 2014
Oil, Gas and Mining

Date: _____
By: 

NAME (PLEASE PRINT) Melissa Luke	PHONE NUMBER 303 323-9769	TITLE Regulatory Technician
SIGNATURE N/A		DATE 11/3/2014



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43013517280000

API: 43013517280000

Well Name: Slade 2-25-2-2WH

Location: 0228 FNL 2468 FEL QTR NWNE SEC 25 TWNP 020S RNG 020W MER U

Company Permit Issued to: NEWFIELD PRODUCTION COMPANY

Date Original Permit Issued: 12/18/2012

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☒ Yes ☐ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

Signature: Melissa Luke

Date: 11/3/2014

Title: Regulatory Technician Representing: NEWFIELD PRODUCTION COMPANY



GARY R. HERBERT
Governor

SPENCER J. COX
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

December 24, 2015

Newfield Production Company
Rt 3 Box 3630
Myton, UT 84052

Re: APDs Rescinded for Newfield Production Company,
Duchesne and Uintah County


Ladies and Gentlemen:

Enclosed find the list of APDs that is being rescinded. No drilling activity at these locations has been reported to the division. Therefore, approval to drill these wells is hereby rescinded effective December 24, 2015

A new APD must be filed with this office for approval prior to the commencement of any future work on the subject location.

If any previously unreported operations have been performed on this well location, it is imperative that you notify the Division immediately.

Sincerely,


Diana Mason
Environmental Scientist

cc: Well File
Brad Hill, Technical Service Manager
SITLA, Ed Bonner



43-047-52434 GMBU 3-36-8-18H
43-013-51750 Shields 1-30-3-2WH
43-013-51781 Gilbert 14-34-2-4W
43-013-51728 Slade 2-25-2-2WH